



Quotation request for excavation and foundation

All quotations must conform to the building code and standards of the cities, which issue the building permit.

Excavation and foundation:

- Excavation and backfilling of the foundations with material from excavation. Should the material not be suitable, other material will be substituted at the customer's expense.
- Excavation and hook up to sewers and water system to a maximum of 25'.
- One sewer drain.
- One storm drain.
- One copper, water main hook up $\frac{3}{4}$ " outside and $\frac{1}{2}$ " inside.
- One truck load of sand for water hook up and sewer. (if necessary)
- Footing 24" wide x 8" thick minimum according to the type of soil.
- 4" drain pipe installed around the footings, covered with $\frac{3}{4}$ " crushed stone.
- Foundation 8" thick x 8' high or 10" thick x 8' high if using brick. (see plan for details)
- Concrete walls 20 M.P.A. With 2 $\frac{1}{2}$ " steel rods in the top part of foundation.
- Pitch covering outside of foundations.
- Concrete floor 25 M.P.A. 3" thick with 15mm (6mil) polythene on bed of crushed stone $\frac{3}{4}$ " \pm 7" thick.
- Floor polishing.
- Prepare opening for windows. (see plan for details)
- Level the part of the lot where the Champoux modular home will be delivered with sand or stone. (Material from excavation can not be used for that purpose.)
- All moving of soil, rocks, stumps, are not included.
- Dynamiting is at customer's expenses.
- Others details: _____

Date of completion: _____

Price for labor and material: _____ \$
Taxes: _____ \$
Total price: _____ \$

Date: _____

Name of contractor: _____

Signature of contractor: _____